

ADDENDUM NO 2
 Issued April 2, 2018

FROM: Seattle Housing Authority
 Mel Henley
 190 Queen Anne Avenue North
 P.O. Box 19028
 Seattle, WA 98109

TO: All Planholders

This Addendum No. 2, containing the following revisions, additions, deletions and/or clarifications, is hereby made a part of the Contract Documents for the above-named project. Bidders shall take this Addendum into consideration when preparing and submitting their response to this solicitation. Receipt of this Addendum shall be acknowledged by inserting its number in the space provided in Section 00300 Bid Form. Failure to do so may deem the proposer as non-responsive.

1. ANSWERS TO SUBMITTED QUESTIONS

Item#	Response
20180402-01	<p>Question – I am unable to locate details for the different types of doors and cameras in the bid documents?</p> <p>Answer – The details were release on Addendum # 1</p>
20180402-02	<p>Question – At Michaelson Manor there is a gate card reader that could potentially be damaged by traffic exiting the garage, should a bollard be placed to protect the card reader on the exit side only?</p> <p>Answer – A bollard is called for in the “NO” detail. Refer to that detail when it is issued in the addendum.</p>
20180402-03	<p>Question – Is it acceptable to powder coat all interior conduit one color (white) as done in phase 1 no matter the existing wall color (see attached specification for paint color)? All exterior conduit will be painted to match existing surface color.</p> <p>Answer – Yes. It is acceptable to powder coat all interior conduit one color as done in Phase 1.</p>
20180402-04	<p>Question – At Nelson Manor the new head end is located in Lounge #1. Please confirm access control to be added to the closet door and the door detail.</p> <p>Answer – This area is being built out to accommodate the head end equipment. There will be NO “AP” door at this location.</p>

20180402-05	<p>Question – At Fremont place please confirm if head end should remain in Office # 2.</p> <p>Answer – Yes. The head end should remain on Office #2</p>
20180402-06	<p>Question – At Ravenna Schools site it was noted that the head end should relocate from the janitors closet to the phone room across the hallway due to space constraint please confirm. If the headend is relocated please confirm door detail AP on the janitor’s closet door should be relocated to the phone room door.</p> <p>Answer – The head end will be moved from the janitors closet and relocated to the phone room across the hallway, there will be NO “AP” door at this location.</p>
20180402-07	<p>Question – For camera KC at Willis house it was noted at the job walk that an existing tree may block the camera view, please confirm the height of the pole and type. If the camera height is to remain will the owner be responsible for trimming the tree?</p> <p>Answer – The type and height of the pole will remain as per the details released on Addendum #1. SHA will keep tree trimmed.</p>
20180402-08	<p>Question – Is each building wired for outside connectivity? If not will the owner be coordinating and providing that?</p> <p>Answer – Each building should have internet connectivity to allow for the federation into the system head end. If it not existing at the time of installation, SHA will be having that service installed.</p>
20180402-09	<p>Question – Should we include a raceway and wire from the demarcation point and the head end or is the owner providing that please provide detail?</p> <p>Answer – This question is not clear. All conduit and wiring should run from the device back to the Rack at the MDF.</p>
20180402-10	<p>Question – On the pricing sheet I noticed that conduit and cable are lump sum breakouts, just wanted to confirm that for the detail breakouts we should not include raceway and wire in that pricing.</p> <p>Answer – The pricing sheet is a living document, and therefore has the ability to be modified. Please provide as much detail as possible in your pricing.</p>
20180402-11	<p>Question – We don’t seem to find any of the door details or camera details in the bid documents, will those be released soon?</p> <p>Answer – Refer to answer for question 20180402-01.</p>
20180402-12	<p>Question – In regards to the cameras, Is the SNV models locked in, or can X series be used. I think SNF8010 will be unavailable, XNF8010RV is the replacement. Also, X series does not have 3MP, only a 2MP and a 5MP.</p> <p>Answer – The model number applied in the detail is the camera that should be used, as they have already been applied at the Phase 1 sites. If at the time of Phase 2 install that specific camera model is unavailable, then we will review the appropriate replacement camera model.</p>

End of Addendum No. 2